



Erratum-ELM-2/013/2017-2018

Kindly be informed that the below mentioned specification has been revised and the closing date has been extended:

1. CLOSING DATE

CLOSING DATE	EXTENDED CLOSING DATE
01 November 2017	03 November 2017

2. SPECIFICATION

SUPPLY AND INSTALLATION OF EXPANDABLE/RETRACTABLE BURGLAR GUARDS AT MACLEAR IPD OFFICES

Back view		
PMU MANAGER Office (W2)	Board room area (W3)	Electricity Manager Office (W2)
1400x1500	1500x1500	1400x1500

Front View			
ROADS & STORM WATER MANAGER Office (W2)	Main Door Door (D3)	Secretary office (W2)	IP&D DIRECTOR Office (W2)
1400x1500	1800x2135	1400x1500	1400x1500

Right View					
IP&D Director (W1)	Right Side Door (D2)	Office No 1 (W2)	Office No 2 (W2)	Office No. 3 (W2)	Electricity manager (W2)
850x600	813x2066	1400x1500	1400x1500	1400x1500	1400x1500

Left View				
Roads & Storm water	Office No. 4 (W2)	Office No. 5 (W2)	Office No 6 (W2)	PMU manager (W2)

manager (W2)				
1400x1500	1400x1500	1400x1500	1400x1500	1400x1500


Toilets Window Measurements (T1)
7 x Windows 500mm x 500mm

NB: All above measurements in millimetres (mm)
Summary

QTY	Window / Door description	Burglar Guard Specification
14	Window 2 (W2)	Expandable Aluminium Security Barrier, Non-Sliding Corrosion and UV Resistant Colour : White 1400mm x 1500mm
1	Window 3 (W3)	Expandable Aluminium Security Barrier, Non-Sliding Corrosion and UV Resistant Colour : White 1500mm x 1500mm
1	Window 1 (W1)	2x 11m Square Aluminium Tubing Horizontal Openings to comply with insurance specification 850mm
1	Door 3 (D3)	Expandable Aluminium Barrier Corrosion and UV Resistant Colour : White 1800mm x 2135mm
1	Door 2 (D2)	Expandable Aluminium Security Barrier Corrosion and UV Resistant Colour : White 815mm x 2070mm
7	Toilets 1 (T1)	1 x 11mm Square Aluminium Tubing Horizontally Laid Openings to comply with insurance specification 500mm

We apologise for any inconvenience

Approved By


.....

H. Mduzulwana (SCM Manager)